
SECTION 39 - MANHOLES

39-1 GENERAL

Storm drain manholes, consisting of precast concrete manholes or saddle manholes as shown on the Plans, shall be in accordance with these Specifications and Standard Drawings.

39-2 PRECAST CONCRETE MANHOLES

39-2.01 Precast Concrete Storm Drain Manholes

Precast manhole barrels, risers, cones, flat tops, and grade rings shall conform to ASTM Designation: C 478 with the additional requirement that the cement used shall be Type II. Manhole sections shall be manufactured without the provision for steps.

Flat slab tops shall be constructed of Class "A-2" concrete conforming to Section 50-5, "Portland Cement Concrete", of these Specifications and shall conform to Standard Drawing SD-7.0.

Unless approved by the City, manhole bases shall be precast when the internal diameter of the largest pipe is less than thirty-three inches (33"). Precast manhole bases shall be placed on a minimum of four inches (4") of three-quarter-inch (3/4") crushed rock conforming to Section 50-16, "Clean Crushed Rock", of these Specifications. Pipe connections to manholes shall be made using a resilient connector conforming to ASTM Designation: C 923. For precast bases the connection shall be made with a flexible compression gasket, which is set during the precast process, or a boot connector. For cast in place bases the connection shall be made with a water stop. All connections shall be water and soil tight. The surface finish shall conform to Section 51-1.03F(2), "Ordinary Surface Finish", of the State Specifications.

When the inside diameter of the largest pipe is thirty-three inches (33") or greater, the manhole base may be cast-in-place. The base shall not be cast higher than six inches (6") above the outside top of the main incoming or outgoing pipe. Concrete used shall be Class "A-2" conforming to Section 50-5, "Portland Cement Concrete", of these Specifications. Slump shall not exceed two inches (2") as determined by the slump cone method of ASTM Designation: C143, or an equivalent slump as determined by Test Method No. California 533. Minimum and maximum wall thickness for the cast-in-place sections shall conform to the following Table 39-1 and shall be strictly adhered to:

SECTION 39 - MANHOLES

TABLE 39-1 MINIMUM/MAXIMUM WALL THICKNESSES FOR CAST-IN-PLACE SECTIONS		
Manhole Diameter(inches)	Minimum Wall Thickness (inches)	Maximum Wall Thickness (inches)
48	5	7
60	6	8
72	7	9
84	8	10
96	9	11

Inside diameters of the cast-in-place portions shall equal the diameter of the manhole specified. Standard precast manhole riser sections and other components as specified in this Section shall be used above the cast-in-place base to bring the manhole rim to grade. Manholes with cast-in-place bases and all of the associated connections and joints shall be capable of passing the leakage test as specified in this Section.

Concrete on the cast portion may be placed against undisturbed earth provided wall thickness requirements are met; otherwise, outside forms shall be required. Forms shall be removed and the structure visually inspected prior to backfill. The surface finish shall conform to Section 51-1.03F(2), "Ordinary Surface Finish" of the State Specifications. Standard concentric cones conforming to ASTM Designation: C 478 shall be used on all manholes shown on the Plans unless otherwise specified. Where depth is insufficient for cones, concentric flat slab tops shall be used.

Joints in precast manhole shafts shall be sealed by buttering the joint space of the previously laid barrel section or base with mortar, or shall be sealed with preformed plastic sealing compound conforming to Federal Specifications SS-S-0021A and installed as recommended by the manufacturer. All joint surfaces shall be thoroughly cleaned prior to placing the sealing compound or buttering with mortar. The inside and outside of mortared joints shall be plastered with mortar and the inside brushed to a smooth finish with a wet brush. Special precautions shall be taken to see that the entire joint space is filled with mortar and is watertight.

Manhole frames and covers shall be of the type and size shown on the Plans and shall conform to Section 50-31, "Storm Drain Castings", of these Specifications, Standard Drawing SD-9 or SD-10 in paved areas or Standard Drawing SD-11 in unpaved areas, and these Specifications, unless otherwise shown on the Plans or specified in the Special Provisions. The joint between the manhole frame and the cone or grade ring shall be sealed by buttering the joint space with mortar, or the joint shall be sealed using an epoxy adhesive. The adhesive shall be as described in Section 95-1.02E, "Epoxy Adhesive for Pavement Markers", of the State Specifications. A concrete collar shall be placed on all manhole frames per Standard Drawing SD-7. The concrete collar shall be Class "A-2" in conformance with Section 50-5, "Portland Cement Concrete", of these Specifications. The in-place depth of the twenty-four-inch (24") manhole opening shall not exceed eighteen inches (18") from the top of the frame to the top of the cone or from the top of the frame to the soffit of the flat

SECTION 39 - MANHOLES

slab top. If the depth of the twenty-four inch (24") opening must exceed eighteen inches (18"), a thirty-six inch (36") frame and cover with the corresponding thirty-six inch (36") manhole components shall be used. The depth of a thirty-six inch (36") opening as described above shall not exceed twenty-four inches (24"). Components for construction of manholes shall be selected to provide the least achievable vertical dimension between the finished frame surface and the top of the cone or soffit of the flat slab top. The depth of precast grade rings or cast-in-place grade rings shall not exceed eight inches (8") on new or reconstructed manholes.

All castings shall be manufactured true to pattern and with satisfactory fit of all component parts. Round frames and covers shall have machined bearing surfaces. All manhole covers which do not fit neatly and bear firmly in the ring will be rejected.

The pipe zone material surrounding pre-cast concrete manholes and extending out minimum of two feet (2') horizontally from the manhole barrel shall be backfilled with Type "D" material (CDF). The Type "D" backfill shall extend a minimum of four feet (4') vertical above the top of the lowest associated pipe or a minimum of one foot (1') vertical above the top of the highest associated pipe, or to the base of the conical section of the manhole barrel and below the subgrade, whichever is greater. The material shall extend horizontally to the edges of the manhole excavation where adjoining trenches do not exist. In no case shall the Type "D" backfill material extend above the base of the conical section of the manhole barrel.

39-3 SADDLE MANHOLES

39-3.01 Saddle Storm Drain Manholes

Saddle storm drain manholes shall not be installed in new facilities. Saddle storm drain manholes shall only be installed in retrofit and repair situations as directed by the City Engineer.

Saddle storm drain manholes shall be constructed in accordance with either Standard Drawings SD-8A (for cast-in-place pipe) or SD-8B (for all other pipe). The concrete shall be Class "A" in conformance with Section 50-5, "Portland Cement Concrete", of these Specifications. Reinforcing steel shall conform to Section 50-30, "Reinforcing Steel, Curb Dowels and Tie Bars", of these Specifications. Manhole frames and covers, risers, cones, grade rings, flat tops, and other features of the manholes shall be constructed in accordance with Section 39-2.01 in this Section of these Specifications.

39-4 MANHOLE TESTING

39-4.01 Storm Drain Manholes

All new manholes shall be tested for leakage after assembly but prior to back-filling around the manhole. The contractor shall furnish all labor, tools, and equipment necessary to make the test and to perform any work incidental thereto. The Contractor shall correct any excess leakage, and repair any damage to the manhole and its appurtenances at the Contractor's own expense.

The manholes shall be tested for leakage by the following method:

Manhole Vacuum Test

SECTION 39 - MANHOLES

All lift holes, connections, and inside and outside joints shall be sealed as described in this Section. All pipes entering the manhole shall be plugged, taking care to securely brace the plug from being drawn into the manhole. The test head shall be placed at the inside of the top of the cone section and the seal inflated in accordance with the manufacturer's recommendations. In the case of flat top manholes, the test head shall be placed at the top surface of the flat top. A vacuum of ten inches (10") of mercury [approximately five pounds per square inch (5 psi)] shall be drawn and the vacuum pump shut off. With the valves closed, the time shall be measured for the vacuum to drop to nine inches (9"). The manhole shall pass if the time is greater than the times listed in the following Table 39-2 for the particular manhole size.

Manhole Size (inches)	Minimum time to drop to 9" Hg (seconds)
48	60
54	67
60	75
72	90
84	105
96	120

If the manhole fails the initial test, necessary repairs shall be made while the vacuum is still being drawn. Re-testing shall proceed until a satisfactory test is obtained.

39-4.02 Manhole Pipe Zone Backfill Over 4ft Deep

The pipe zone material surrounding manholes and extending out a minimum of two feet (2') horizontally from the manhole barrel shall be backfilled with Type "D" material (CDF). CDF material must be in contact with firm and stable material. The Type "D" backfill shall extend a minimum of four feet (4') vertical above the top of the lowest associated pipe, or a minimum of one foot (1') vertical above the top of the highest associated pipe, or to the base of the conical section of the manhole and below the subgrade, whichever is greater. The material shall extend horizontally to the edges of the manhole excavation where adjoining trenches do not exist. In no case shall the Type "D" backfill material extend above the base of the conical section of the manhole barrel.

39-5 ADJUST STORM DRAIN MANHOLES TO GRADE

Existing manholes shall be adjusted to grade or elevation as indicated on the Plans and shall conform to Section 71 of the State Specifications, with the exception that raising devices are not allowed. Adjustment may be made by utilization of precast grade rings or by a cast-in-place ring. Cast-in-place rings shall be Class "A-2", in conformance with Section 50-5, "Portland Cement Concrete", of these Specifications. The cast-in-place rings shall have a minimum height of three inches (3") and a maximum of six inches (6"). The concrete pour shall extend to one and one-half inch (1.5") below the top of the frame.

Adjusting manholes to grade within publicly used traffic lanes shall be completed, including

SECTION 39 - MANHOLES

placing paving material around and to the level of the frame and cover, by the end of the same day on which work is started. If permanent pavement backfill cannot be completed by the end of the work day, the Contractor shall place temporary paving material to the finished grade level of the frame and cover. The Contractor shall maintain the temporary paving smooth and level with the frame and cover until such time as the permanent paving is placed.

39-6 RECONSTRUCT STORM DRAIN MANHOLES

The Contractor shall reconstruct storm drain manholes as shown or specified in the Contract.

In order to access and maintain storm drain facilities, the maximum depth of a twenty-four inch (24") manhole opening is eighteen inches (18") and the maximum depth of a thirty-six inch (36") manhole opening is twenty-four inches (24"). The depth of the opening is measured from the top of the finished grade of the frame to the top of the cone or to the soffit of the flat slab top. When the depth of the opening exceeds this requirement, it is necessary to reconstruct the manhole by placing additional barrel sections to bring the top of the cone or soffit of the flat slab top to within eighteen inches (18") of the finished surface.

The Contractor shall remove and dispose of the existing frame and cover and demolish the remaining structure down to the elevation where a standard precast barrel section or combination of barrel sections will bring the top of the cone or soffit of the flat slab top to within a maximum of eighteen inches (18") of the finished surface or as indicated on the Plans. The resulting debris and hardware become the property of the Contractor. Standard precast barrel sections are available in depths of twelve, eighteen, twenty-four, thirty-six, and forty-eight inches (12", 18", 24", 36", and 48"). The top of the remaining structure shall be trimmed to provide a suitable foundation for the new barrel components. The joint between the existing structure and the new component shall be sealed in conformance with Section 39-2.01, "Precast Concrete Storm Drain Manholes" in this Section of these Specifications. If not called out on the Plan, it is the responsibility of the Contractor to determine whether the existing structure is precast, cast-in-place, or a precast structure with a cast-in-place base.

39-7 ABANDON STORM DRAIN MANHOLES

When indicated on the Plans or directed by the City, storm drain pipes, manholes, and other structures shall be abandoned in conformance with Section 15-1.04, "Abandonment of Conduits and Structures", of these Specifications.

39-8 MEASUREMENT AND PAYMENT

The quantity of storm drain manholes, consisting of precast concrete manholes or saddle manholes, will be measured by the unit.

The unit price paid for storm drain manholes includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing sewer manholes, complete in place, including excavation and backfill, manhole bases, mortar, concrete, reinforcement, and acceptance testing, as shown or specified in the Contract, specified in these Specifications, and directed by the City.

The quantity of storm drain manholes, consisting of precast concrete manholes or saddle manholes, will be measured by the unit.

The unit price paid for storm drain manholes includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in

SECTION 39 - MANHOLES

construction of storm drain manholes, complete in place, including excavation and backfill, manhole bases, mortar, concrete, reinforcement, and acceptance testing, as shown or specified in the Contract, and as directed by the City.

Payment for adjusting storm drain manholes shall conform to Section 71-5.04 of the State Specifications, with the following exceptions: 1) the unit price paid includes all necessary excavation, backfill, sealing, and concrete; and 2) the unit price paid will be the average of all depths and limits of adjustment required.

The unit price paid for storm drain manhole reconstruction includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in reconstructing manholes, complete in place, including excavation and backfill, demolition, disposal, mortar, concrete, and reinforcement as shown or specified in the Contract, in these Specifications, and as directed by the City.